

Scope: At a location on Yorktown Dr and Brassie Dr, the Village is creating a 'dog park' which requires the installation of approved chain-link fencing and associated gates.

- All fencing is to be five (5) feet in height.
- All terminal posts, aka 'End', 'Corner', and 'Gate' Posts will be 2-1/2" (2-3/8" actual outside diameter).
- All line posts, aka 'Intermediate' - 2" OD (1-7/8" Actual) for 5' of height.
- Top/Bottom/Center Rail will be 1-5/8" OD (1-5/8" Actual).
- All posts must be capped.
- All posts rails and appurtenances shall be hot-dip galvanized and powder coated black.
- All posts must be placed no more than 10' on center, 42" below grade encased in a 12" diameter 4000 psi concrete footer.
- All ties shall be hot-dip galvanized and powder coated black
- Fabric fence mesh shall be 2" X 2" diamond 9-gauge core vinyl coated black chain link fence. The vinyl coating should be thermally fused and bonded. Referencing the site plan rendering, the fence will be approximately 1110 linear feet.

It will include three (3) 10' gates and four (3) 4' gates.

- All gates should include installation of a lockable latch. Latches must be included and allow for a pad lock. All posts rails and appurtenances shall be hot-dip galvanized and powder coated black.

Installation of specified fencing shall be completed by 30 April 2022. Any delays or changes to this will need to be pre-approved by the Director of Public Works.

All Concrete flatwork (sidewalks/pads) to be completed by others and is not part of this RFP.

